



# SITALKUCHI COLLEGE

P.O-Sitalkuchi, Dist- Cooch Behar  
Pin- 736158, West Bengal  
**Phone- 03583-263351, Fax- 03583-263351**  
**Website- [www.sitalkuchicollege.ac.in](http://www.sitalkuchicollege.ac.in)**  
**E-mail- [csitalkuchi@yahoo.com](mailto:csitalkuchi@yahoo.com)**

---

## **Tender notice No. 4/2018-19**

Dated 18.02.2019

Sealed quotation is invited for the work of **Steel railing for Balcony and Staircase** in the attached schedule as per terms and condition stated under here:

1. Quotation in sealed cover superscribed "**Steel railing for Balcony and Staircase**" should reach the office of the undersigned by **4PM on 23.2.2019** be opened at 2 PM ON 26.02.2019 in the presence of representatives of purchase committee. The price quoted should be in the **enclosed format only** (Annex). Incomplete quotation shall be liable to be rejected.
2. The rates quoted shall include all charges, such as transport and others.
3. In case of any tax to be levied, that should be stated clearly.
4. All goods shall be received subject to approval on inspection.
5. The institution reserves all right to accept or reject summarily any or all quotation(s) in whole or in part without assigning any reason whatsoever.
6. The institution takes no responsibility for delay, loss or non receipt of quotation.
7. The bidder must mention the specified **time of completion** of the project.
8. Any **photograph of same kind of work** with certificate from the owner is required to be attached.

(Dr. Afzal Hossain)  
Principal  
Sitalkuchi College

ANNEXURE

WORK DETAILS

NAME OF THE PROJECT: **Steel railing for Balcony and Staircase**

Sl. No.	Description	Quality	Quantity	Rate	Unit	Amount
1.	Supply of providing and fixing Stainless Steel Railing made of hollow tubes, channels, angles, balls etc. including welding buffering (wherever required) and fitting the same with necessary Stainless steel nuts and bolts complete i.e fixing the railing with necessary accessories along the balcony	Jindal 304 (18 Gauge) with 2" railing Pipe on the top along with 3/4 nos. 1.5" vertical pipe & 3 nos.75" horizontal railing pipe. The total height will be of 3.5 feet.	593 feet (approx)		Running feet	
2.	Supply of providing and fixing Stainless Steel Railing made of hollow tubes, channels, angles, balls etc. including welding buffering (wherever required) and fitting the same with necessary Stainless steel nuts and bolts complete i.e fixing the railing with necessary accessories along the Staircase	Jindal 202 (18 Gauge) with 2" railing Pipe on the top along with 3/4 nos. 1.5" vertical pipe & 3 nos.75" horizontal railing pipe. The total height will be of 3.5 feet.	566 feet (approx)		Running feet	

Labour Charge : .....

Total Amount :

(In Words.....)

Time for completion of the Project:

Any other comments:

Signature

Name of the Company (with Seal)